

Management of Temporary Works.

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
55	Activities involving Temporary Works	Management of Temporary Works Failure of structure Collapse of excavation	Employees Contractors Public Visitors	<ul style="list-style-type: none"> Ensure competent duty holders are appointed to manage the temporary works process, including: <ul style="list-style-type: none"> Temporary Works Designer (TWD). Temporary Works Co-ordinator (TWC). Temporary Works Supervisor (TWS). All Temporary works must be in accordance with the Telecom Division Temporary Works procedure. TWC will ensure that a schedule of planned TW is produced for planned works. TWC will ensure a design brief is presented to the TWD and then ensure the agreed design is utilised at site level and understood by the appointed TWS. TWS is to ensure that the TW agreed are constructed, loaded and stripped as per the design. Use of the Telecom Division's excavation permit controls will be used to ensure the TW process is followed for all excavations greater than 2.5m deep. 	Low