A site Risk Assessment must be carried out before commencing work. All appropriate PPE must be worn.

Drum Storage

- Select position for storage to ensure security and public safety.
- · Position drum (with fibre / cable on or entry) on level firm ground
- Chock drum (with fibre / cable on or entry) to prevent movement.

A drum with or without cable, Must Not be stored on its side.

Drum Movement

- · Ensure the route of movement is clear.
- Movement of drums shall be a minimum of two person operation.
- · Use kick bars to slew drum.




- Mechanical lifting devices **must** be used where practicable to move drums.
- Movement routes must be clear and free of obstacles and persons.
- A Banks Person/Signaller/Slinger must be used.

Dispensing

- Fibre / cable must only be dispensed using an appropriate drum trailer or cable jacks.
- · Position jacks on firm level ground.
- Do not pull downhill.
- Fibre / cable must not be dragged over rough surfaces
- Fibre / cable must be pulled from the top of the drum only.
- Position drum trailer and vehicle on level ground.
- Ensure vehicle hand break is on and in gear.
- Ensure drum spindle is secured and cable drum is free to rotate.
- Fibre / cable routes must be clear and free of obstacles and persons.
- All equipment must be fit for purpose, tested, in date and suitable for the task.



DO NOT PULL CABLE WITH MINI EXCAVATOR OR VEHICLES!



MGroupServices
Telecom Division