Exposure to Asbestos.

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
06	All work activities where there is a risk of coming into contact.	Unplanned exposure to Asbestos containing materials, such as pipes, cement panels, vinyl tiles, insulation materials pipes / sheets etc. Risks of dust inhalation, particularly when material is damaged, cut or otherwise disturbed.	Employees Contractors Public Visitors	 Morrison Telecom Division does not undertake 'licensed' Asbestos work. Only licensed contractors must undertake the work. When working in premises, refer to the Asbestos register before entering the site. If the presence of Asbestos can affect the work, consult your Line Manager. In the event of encountering Asbestos containing materials during the course of work operations, take the following actions: - Stop Work and contact your Line Manager or Team Leader. Ensure that an approved service provider is used for the removal of any Asbestos containing materials. During works, be aware of common areas where Asbestos may be present, e.g. cement panels, vinyl tiles, insulation materials etc. If there is suspected Asbestos, ensure Respiratory Protective Equipment (Face Fit Tested FFP3 disposable mask or half mask with P3 filter) is worn. Avoid contamination by taking rest and meal breaks away from the work area. Information, instruction and training for Asbestos awareness provided to employees who may disturb Asbestos during any normal work. 	Low