

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
67	All work activities	<b>Low Risk Manholes</b>  Potential for the presence of gas / low oxygen	Employees and other contractors	<ul style="list-style-type: none"> <li>- All personnel will be fully trained with in-date confined space training appropriate to type and level.</li> <li>- Must be a structure with low risk of falling.</li> <li>- Entrance shaft no longer than 3 metres.</li> <li>- Distance from ground level to structure floor less than 6 metres.</li> <li>- Work place must have ease of access and be less than 10 meters from entry / exit point.</li> <li>- Work-place no more than 2 meters from the hose end gas test with four-head GDU used as continuous monitor.</li> <li>- Ease of contact with the Top Person. No environmental hazard present – pre-start risk assessment.</li> <li>- Air blower, with second hose if necessary. A GDU must be placed at the blower to monitor traffic emissions.</li> <li>- First Aid Kit present.</li> </ul>	Low