

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
77	All work activities Plant and Vehicle Movement	Contact with moving plant and vehicles	Employees, Other Contractors, Members of the Public	 Hierarchy of control. Exclusion zones. Agreed communication between plant controller and operator. Ensure clear line of sight at all times between plant controller and operator. Assessment of hazards within the vicinity e.g. excavations, overhead apparatus, people etc. Safe system of work e.g. traffic management plan. Trained and authorised plant controller. Reversing controls. 	Low