

Site Security.

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
44	All work activities and including out of hours (downtime)	Unauthorised access Vandalism Tampering Risks of interference with plant and equipment, Entering excavations	Employees Contractors Public Visitors	<ul style="list-style-type: none"> • Work areas must have full barrier protection around the site boundary to prevent entry by the public. • Excavations and chambers must have full barrier protection, adequate signage and lighting in place for the full duration of the works. • Maintain sites in accordance with the Safety at Street Works and Road Works - A Code of Practice. • Where available, ensure CCTV and alarms are in constant operation. • Ensure all gates and temporary compounds remain locked. • Roadside lighting must be in good working order and provide full illumination of the worksite. • Safely immobilize plant and vehicles with keys removed when not in use. • Remove all ladders, work platforms etc and store in a secured area or off-site to prevent use by trespassers. • Consider additional security measures where required. 	Low