

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
63	All work activities involving Temporary Works	<b>Management of Temporary Works</b>  Failure of Structures, Excavation Collapse	Employees, Other Contractors, Members of the Public	<ul style="list-style-type: none"> <li>- Appointment of competent duty holders to manage the Temporary Works (TW) process</li> <li>- The senior manager to the contract shall ensure the appointment of suitable competent resources from either an internal and / or external source to cover the roles of:               <ul style="list-style-type: none"> <li>• Temporary Works Designer (TWD).</li> <li>• Temporary Works Co-ordinator (TWC).</li> <li>• Temporary Works Supervisor (TWS).</li> </ul> </li> <li>- TWC will ensure that a schedule of planned TW is produced for planned works.</li> <li>- TWC will ensure a design brief is presented to the TWD and then ensure the agreed design is utilised at site level and understood by the appointed TWS.</li> <li>- TWS is to ensure that the TW agreed are constructed, loaded and stripped as per the design.</li> <li>- Use of MTS excavation permit</li> </ul>	Low

				controls will be used to ensure the TW process is followed for all excavations greater than 2.5m deep.	
--	--	--	--	--	--