

No	Activity	Hazard	Person(s) in Danger	Control Measures	Residual Risk Rating
16	Working in the vicinity of overhead cables	Overhead Cables  Coming into contact through improper use of plant / equipment	Employees, other contractors and public	<ul> <li>Full compliance with Health and Safety Executive Guidance Note GS6.</li> <li>Carry out a site specific Risk Assessment.</li> <li>Where practicable request the overhead cable height.</li> <li>Be aware of different exclusion zones for pylons and poles.</li> <li>Keep plant and equipment outside the exclusion zone.</li> <li>Use goal posts and height restrictions for grab / excavator booms.</li> <li>Be aware in damp or wet conditions because it will increase risk of arcing.</li> <li>Make sure jib / boom are stowed before moving.</li> <li>Be aware of vehicle height restrictions.</li> </ul>	Low