


VMHP3 Cabinet


Front Elevation




Left Elevation



Plan View - Root Base Duct Configuration



Side Section - Duct Configuration



Notes/Key:

1. All civils works to be carried out in conjunction with the Virgin Media Specifications.
2. Earth Rod installation to be carried out in conjunction with NSH3529.
3. All ducts to be green unless otherwise stated.
4. Earth Rod to protrude no more than 75mm.
5. Ducts to extend 50mm above concrete base.
6. C30/20 concrete to be used to cast the base.
7. All reinstatement to comply with NRSWA.
8. Finished root level to be 75-100mm above ground level.
9. Chamber detail shows ducts in wall adjacent to the cabinet.
10. All dimensions in millimetres unless otherwise stated.

Version 1.1
Last Updated 07/05/13

Created by:
Stephen Scott

Drawing Title: VMNB0022

Authorised by:
Nigel Myers

VMHP3 Cabinet, Duct Configuration and Root Base

For any feedback on this drawing
please contact us at...

technicaldrawings@virginmedia.co.uk



© 2012 Virgin Media Ltd
All rights reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means (Electronic, Mechanical, Photocopying, Recording or otherwise) without the prior written expressed consent of the Company. Once printed this document is uncontrolled and subject to change without notice.

This document was created with Win2PDF available at <http://www.win2pdf.com>.
The unregistered version of Win2PDF is for evaluation or non-commercial use only.
This page will not be added after purchasing Win2PDF.